

**Specifications for Bid- Ellis Clark Oil Tank Removal  
5 Minortown Road, Woodbury CT 06798**

Region 14 Schools is soliciting bids for the removal and disposal of a 5,000 gallon fiberglass oil tank. The contractor will be responsible for the following:  
Specifications are available on the RSD 14 website ([www.ctreg14.org](http://www.ctreg14.org)) or at the RSD #14 Central Office located at Woodbury Middle School, 67 Washington Ave., Woodbury, Ct 06798. Questions and site visits can be arranged with Michael Molzon, Facilities Director, at 203-263-4330.

1. Excavate to the top of the tank. Open mainway, enter tank, clean and vacuum. Vacuum oil lines and disconnect from the building. Oil lines should also be disconnected in the boiler room at the lowest possible point and vacuumed removing all oil.
2. Remove tank and dispose. Leave concrete pad if possible.
3. Take five (5) samples per DEEP specifications. The contractor will contact DEEP and the Town of Woodbury Fire Marshall's Office to coordinate testing and clearance and final filing with DEEP.
4. Fire Marshall to inspect the site.
5. Remove oil lines to the building at the foundation and cap lines off. Remove and dispose of oil lines. Remove and dispose of vent pipe. Remove and dispose of fill/spill box.
6. Backfill the hole with suitable backfill material compacted in 1' lifts.
7. Finish off all disturbed areas with 5" of loam and then mulch the area with a mulch that matches existing material. The area should blend in with existing grades.
8. The contractor will protect the work area with suitable safety fencing during the project.
9. Care should be taken to minimize the impact on surrounding sidewalks. If the site excavation impacts the sidewalks, the contractor will be responsible for saw cutting and removal.
10. During the backfilling, the sub grade will be prepared and compacted for reinstallation of the sidewalks.
11. Care should be taken to avoid damage to the buildings main water line, gas line, and any other utilities.
12. All concrete sidewalks and retaining walls shall be properly protected to avoid any damage during construction. The sidewalks and retaining walls shall be thoroughly cleaned and restored to original condition at the end of the project.
13. The contractor shall call for underground utility mark out.
14. No smoking is allowed on school grounds per Connecticut State Law.